$\textbf{Organisation Chain}: \\ \textbf{THE WEST BENGAL POWER DEVELOPMENT CORPORATION}$ LTD.||SAGARDIGHI THERMAL POWER PROJECT (SgTPP)

Tender Id: 2019_WBPDC_215782_1

Tender Reference Number: WBPDCL/SGTPP/NIT/E1241/18-19

Procurement of Complete Coal Nozzle Assembly of stage- 1 (2 X 300 MW) for **Tender Title:**

Sagardighi Thermal Power Project, WBPDCL

Corrigendum Type: Technical Specification

Detail Information:

- 1) For item SI. No-5 Technical specification will be as per Tender Document as there is some difference in Drawing.
- 2) PMI Test for item SI.No-5 will be for alumina content.
- 3) Test of Alumina ceramic Tiles will be as per attached SQP (Standard Quality Plan) for item SI.No-5
- 4) Inspection (by TPI /WBPDCL representative/Joint Inspection) will be done to check all the properties of Alumina Ceramic Tiles being used for lining of Coal Nozzle Assembly as per attached SQP by destructive test at vendor's works. TPI cost will be borne by Bidder.
- 5) All the Ceramic Tiles will be of weldable ceramic tiles .welding to be done with high temperature weld plug.

All other Terms & Conditions as per Tender Document will be remain unchanged.

		Manufacturer's Name & Address (es)				STANE	DARD QUALITY PLAN				PROJECT :				
Manu				ALUMINA CERAMIC LINED			QP No. :				CONTRACTOR:			R:	
			ITE M:				DATE:								
							PAGE: 1 of 1								
SI.	Compon ent /	Characteristics	Cla ss of Che ck	Type of Check	Quantum	of Check	Reference		Format of		Agency**				
No.	Operatio n				М	T/C	Document	Acceptance Norm	Record		М	T	С	Remarks	
1	2	3	4	5	5 6		7	8	9 D			10		11	
1.0	RAW MATE	ITERIAL													
1.1	Steel Plate	Chemical Analysis	В	Verificatio	100%	100%	IS-2062 Gr E250 Br.	IS-2062 Gr E250 Br.	Mill Test Certificate		P	V	v		
1.1		Mechanical Properties		n	100%					•	Р	V	V		
2.0	INSPECTIO	ON OF FABRICATED CASING													
2.1	Dimensi ons	Visual Inspection & Dimensions	А	Mesurem ent	100%	10%	As per Approved Drawing	As per Approved Drawing	Fabricatio n Report		Р	٧	R		
		Welding Process	В	Review of WPS,			4000/		ASME Sec IX WPS,			Р	V	R	
2.2	Welding	Welder's Qualification	В	WPQ	100%	100%	ASIVIE	SEL IA	WPQ	•	۲	V	ĸ	Refer Note-	
		Welding - Butt Weld Joint	В	DPT	10%	10%	ASME Sec V	ASME B31.1	DP Test Report	•	Р	W	W		
3.0	.0 FINAL INSPECTION OF CERAMIC LINED EQUIPMENT														

3.1	Final Assembl y	Dimensional	А	Visual & mesurem ent	100%	10%	As per Approved Drawing	As per Approved Drawing	Final Inspectio n Log Sheet	Р	W	W	СНР	
3.2	Step & Gap between Tiles	Visual Inspection	А	Visual	100%	100%	2 mm (M	aximum)	Lining Report	Р	W	w		
		Alumina Content	А	Chemical	5 Samples /Lot	5 Samples / Lot	Approved Ceramic Datasheet	>90%		Р	W	w	Alumina Content to be witnessed on XRF. Vendor to ensure availability of Certified Reference Materials for onsite calibration before testing	
	Testing of Ceramic Tiles	Bulk Density	А	Physical	1 Sample / Lot	1 Sample / Lot	Approved Ceramic Datasheet	3.6 gm/cc (Minimum)	Manufact	Р	W	W		
3.3		Hardness	А	Physical	1 Sample / Lot	1 Sample / Lot	Approved Ceramic Datasheet	<u>></u> 9 Moh's	urer's Test Certificate	Р	W	W		
		Water Absorption	А	Physical	1 Sample / Lot	1 Sample / Lot	Approved Ceramic Datasheet	0.1% (Maximum)		Р	W	W	Refer Note -	
		Compressive Strength	А	Physical	1 Sample / Lot	1 Sample / Lot	Approved Ceramic Datasheet	10,000 Kg/cm ² (Minimum)			Р	W	W	1&2
		Flexural Strength	А	Physical	1 Sample / Lot	1 Sample / Lot	Approved Ceramic Datasheet	2,200 Kg/cm ² (Minimum)		Р	W	W		
		Abrasion resistance test by Rubbing	Α	Physical	1 Sample / Lot	1 Sample / Lot	Approved Ceramic Datasheet	0.1 gm (Maximum)			Р	w	W	
		Color	А	Visual	100%	100%	White	White		Р	W	W		

3.4	Tile Thickne ss Check	Dimensional	А	Mesurem ent	100%	10%	As per Approved Drawing		Test Report		Р	W	W	Refer Note- 4
3.5	Identific ation and Marking	Standard Marking and Stamping	В	Verificatio n & Stamping	100%	-	Manufacturer's Standard	Manufacturer's Standard	List of material with Identificati on		Р	1	-	
3.6	Painting	Visual Inspection	В	Visual	100%	10%	As per PO Technical Specifications / Manufacturer's Standard		Painting Report		Р	R	R	
4.0	MDCC	Issue of MDCC	А	Review of Inspection records	100%	100%	As per WBPDCL Approved Drawing & MQP	As per DPSI Approved Drawing & MQP	MDCC		Р	٧	٧	Refer Note- 6
		######################################	#####	************	#########	*****	#################	######################################	DOC	#####	####	####	######################################	######################################
	CI : Class (A : Critical, B : Major, C : Minor)								NO.:					CAT
		** M : Manufacturer, T: Third Party Agency, C: Buyer P: Perform, W: Witness, V: Verification, R: Review, CHP: Customer Hold Point	form, W : Witness, V : Verification, R :						Owner's Logo					

	IR : Internal Inspection Reports, MTC: Material Test Certificate								
Manufacturer	* Records, Identified with Tick (\cdot) shall be essentially Included in QA Documentation				FOR				
SIGNATURE		•			OWNER'S USE	REVIEWED BY	APPROVE D BY	APPROVAL SEAL	